

**MISSOURI PUBLIC SERVICE COMMISSION
MANUFACTURED HOUSING DEPARTMENT
APPROVAL OF ANCHORING SYSTEMS**

IMPERIAL STAMPING COMPANY

MHA #	SB #	DESCRIPTION	SOIL TYPE	DUAL STRAP
MHA-2	MHA-SB-2	5/8" X 48" Single 6" Helix Anchor	2, 3, 4	NO
MHA-6	MHA-SB-6	5/8" X 30" Double 4" Helix Anchor	2, 3	NO
MHA-8	MHA-SB-8	3/4" X 48" Single 6" Helix Anchor	2, 3, 4	NO
MHA-10	MHA-SB-10	3/4" X 48" Double 4" Helix Anchor	2, 3	NO
	MHA-SB-7	11/16" x 30" Double 4" Helix Anchor	2, 3	NO
MHA-12	MHA-SB-12	3/4" X 30" Double 4" Helix Anchor	2, 3	NO
MHA-15-36	MHA-SB-15-36	Two 11/16" x 36" rods, cross drive rock anchor	1	YES
MHA-15-48	MHA-SB-15-48	Two 11/16" x 48" rods, cross drive rock anchor	1	YES
MHA-16	MHA-SB-16	Two 11/16" x 48" rods, cross drive rock anchor	1	YES
MHA-16A	MHA-SB-17	Two 11/16" x 36" rods, cross drive rock anchor	1	NO
MHA-21	MHA-SB-21	Single Head Patio Anchor	Concrete	NO
MHA-22	MHA-SB-22	Double Head Patio Anchor	Concrete	NO
MHA-26	MHA-SB-26	Double Head Hook Anchor	Concrete	NO
MHA-58	MHA-SB-58	3/4" x 36" Single 6" Helix	2, 3, 4	
MH-40		Tension Tube		
	SB	Split Bolt		
MHA-39-L		Pre-assembled Frame Buckle with Strap		
MHA-42-L		Pre-assembled I Beam Adapter with Strap		
MHA-SD-1		Stabilizing Plate		
MHA-SD-2		Stabilizing Plate		

STANDARDS FOR INSTALLATION:

- 1) Anchors and all components must be installed per manufacturer's instructions.
- 2) Anchors are approved for designated soil type only.
- 3) One strap per anchor unless the anchor is approved for dual strap use.
- 4) Consult manufactured home set up instructions for number of tie downs, over the roof tie downs (if required), and tie down spacing.

DATE: August 9, 1996



JAMES PHILLIPS
DIRECTOR
DEPARTMENT OF MANUFACTURED HOUSING,
RECREATIONAL VEHICLES AND MODULAR UNITS

The system being used on your home is _____.